

11. All operations conducted on the premises, including the warming up, repair, arrival, departure or running or trucks, earthmoving equipment, construction equipment and any other associated equipment shall be limited to the period between 7:00 A.M. and 5:00 P.M. everyday unless otherwise approved by the City of Coeur d'Alene.

12. All existing improvements including curb and gutters, sidewalks, asphalt, concrete or P.C.C. paving, which are being joined or matched in connection with this project shall be joined or matched in a manner satisfactory to the City Engineer, including necessary sawcutting, removal, replacement and capping.

13. No revisions shall be made to these plans without the approval of the City Engineer.

14. Compaction testing shall be performed on the following:

- Utility trench backfill
- Roadway embankment
- Curb and gutter subgrade
- Road subgrade
- Road base
- Asphalt paving

The City may require additional testing if it deems necessary. Compaction frequency shall generally adhere to the following guidelines:

- Embankment - 1 per 50 cy
- Trench - 1 per 50 cy located in pipe zone, mid-depth, surface, and around manholes.
- Subgrade
- Road base - 1 per 750-1000 sf
- Asphalt paving
- Curb and gutter - 1 per 75-100 lf

REVISION	APPROVED	DATE	CITY OF COEUR D'ALENE STANDARD DRAWING	APPROVED BY:
			GENERAL NOTES PAGE 2	 CITY ENGINEER, PE 7432
				DATE: 4/1/08
				DWG NO. M-23