

9. Prior to placing of asphaltic concrete, the following shall be completed:
- A. Provide compaction test results for base material to the City's Engineering Inspector.
 - B. Obtain authorization from the City Engineering Inspector to proceed with Asphalt paving. The City Engineering Inspector shall be notified at least forty-eight (48) hours prior to placement of Asphalt paving.
 - C. Obtain approval of all underground utilities which will lie under the pavement.
10. Placement of Asphaltic Concrete shall be observed by a representative of the Engineer of work.
11. Asphaltic Concrete shall be compacted to at least 92% of the maximum theoretical density – AASHTO T209-94.
12. Prior to approval by the City, the pavement shall be water tested for proper drainage and approved by the City Inspector.
13. The City Engineer may require the pavement sections shown on the plans to be verified by the "R" value tests taken from the exposed subgrade.
14. The City Engineer may require coring of the asphalt pavement to verify pavement thickness or density.

REVISION	APPROVED	DATE	CITY OF COEUR d'ALENE STANDARD DRAWING	APPROVED BY:
			PAVEMENT NOTES PAGE 2	 CITY ENGINEER, PE 7432
				DATE: 4/1/08
				DWG NO. M-25