



**NOTE:**

1. NO BLOW OFF PORTS ARE ALLOWED UPSTREAM OR DOWNSTREAM OF THE AVB. THE DEVICE MUST BE REMOVED FROM THE SYSTEM PRIOR TO BLOWING OUT THE IRRIGATION SYSTEM.
2. NO MANUAL OR AUTOMATIC VALVES ALLOWED DOWNSTREAM OF AVB.
3. AVB CANNOT BE PRESSURIZED MORE THAN 12 HOURS IN A 24 HOUR PERIOD.

REVISION	APPROVED	DATE	CITY OF COEUR d'ALENE STANDARD DRAWING	APPROVED BY:
			<b>APPROVED ATMOSPHERIC VACUUM BREAKER INSTALL</b>	<i>Wendy Robles</i> 4/20/15 CITY ENGINEER, PE 7432 DATE:
				DWG NO. W-22