



**NOTE:**

1. NO BLOW OFF PORTS ARE ALLOWED UPSTREAM OR DOWNSTREAM OF THE PVB ASSEMBLY. THE ASSEMBLY MUST BE REMOVED FROM THE SYSTEM PRIOR TO BLOWING OUT THE IRRIGATION SYSTEM.
2. MANUAL OR AUTOMATIC VALVES ALLOWED DOWNSTREAM OF PVB.
3. MAY BE PRESSURIZED FOR MORE THAN 12 HOURS IN A 24 HOUR PERIOD.

REVISION	APPROVED	DATE	CITY OF COEUR d'ALENE STANDARD DRAWING	APPROVED BY:
			<p><b>APPROVED PRESSURE VACUUM BREAKER ASSY.</b></p>	 CITY ENGINEER, PE 7432
				DWG NO. <span style="font-size: 1.5em;">W-23</span>
				DATE: 4/20/15